



GRINER ENGINEERING, INC.

1628 FIRST AVENUE NORTH
ST. PETERSBURG, FLORIDA 33713

PHONE: (727) 822-2335
FAX: (727) 821-3361

ADDENDUM NO. 1

PROJECT: St. Petersburg College
Health Education Center Ductwork Repair and Replacement
GEI No. 11066

DATE: May 9, 2013

DRAWINGS

1. Sheet M1.1
Refer to Scope of Work note #3 for removal and replacement of ceiling tiles.
2. Sheet M2.4
Work related to RTU-4 is limited to duct cleaning; no pre-test of system or duct pressure tests are required. Where openings are made in the ductwork for duct cleaning; the patching of the ductwork will be required to be inspected before covering the patch.
3. Sheet M2.4
Duct sealing of duct cleaning access openings shall be performed as follows. Provide 20 gauge galvanized steel duct to overlap each edge of opening by one-inch. Where ductwork is internally insulated the patch shall have one-inch interior duct insulation applied. Provide duct sealant between patch and ductwork. Secure patch along each side of patch with sheet metal screws located a minimum of two-inches from corners and a maximum of four-inches apart.
4. Sheet M5.1, Specification Section 15950
Ductwork pressure testing and Test and Balance work will be provided by St. Petersburg College by an independent agency. The Test and Balance work shall be performed prior to the installation of any external insulation.
5. Fire Alarm System
Fire alarm will be taken off-line by St. Petersburg College employees upon notification by the Contractor. The Fire Alarm shall be placed back on-line for any unoccupied periods of time.

End of Addendum No. 1