

ADDENDUM #1
CONCRETE SKID PAD REPLACEMENT
ITB #SPC02-17-18
St. Petersburg College
Clearwater, Florida
1/30/2018

Modify Drawing A-1, Note 1. To read:

“sawcut perimeter of existing concrete skid pad and remove concrete and subbase to a depth of 6” +/- . Form and install new 6” reinforced concrete slab as shown in detail 2 &3 on A-2. Dispose of demolished material in a safe and legal manner. Remove forms and patch asphalt as required.”